

Church Void

Existing opening blocked up in studwork on the room side. Doors retained to church side (Spec. Ref: 11.0)

New stairs up to gantry
14 No. Risers @ 195
13 No. Goings @ 225
(Spec. Ref: 13.0)

Proposed New steel frame sound and light gantry to structural engineers details (Spec. ref: 15.0)


Floor to consist 18mm chipboard floor fixed to timber joists at 450mm centres, joists built into wall and fixed to m/s joist hangers welded to steel frame. (Spec. ref: 15.0)

Existing opening blocked up in studwork (Spec. Ref: 11.0)

Rooflights over retained and refurbished

Flat roof over new external yard (Spec. Ref: 19.0)

COPYRIGHT ©
This drawing is copyright and issued to you in confidence. It must not be copied, used or disclosed, in whole or in part, to third parties without our written permission. It remains the property of JUSTIN SMITH ARCHITECT LIMITED and must be returned on request. ©
NOTE: All dimensions are in millimetres unless stated otherwise. If in doubt ask. Do not scale from this drawing.
DRAWING INFORMATION
This CAD drawing is plotted from file: A10-009/A2.1/205
This CAD drawing contains the Xrefs: A10-009/A2.2/Plan_+1; plan_site



REVISIONS	NOTES

CLIENT Paul Pegg	JOB NO. A10-009
PROJECT Refurbishment at; Mackworth Community Centre, Mackworth	DWG. NO. 205
DRAWING Proposed First Floor Plan	REV.
DATE July; 2010	SCALE 1:50
DWG. SIZE A2	DRAWN SCG
STATUS Production Info.	

Justin Smith Architect Limited
Friar Gate Studios,
Ford Street, Derby, DE1 1EE
T: 01332 258350
E: mail@justinmitharchitects.co.uk
W: www.justinmitharchitects.co.uk

JUSTIN SMITH ARCHITECTS